State of Ohio Environmental Protection Agency

RE: FINAL PERMIT TO INSTALL **CERTIFIED MAIL**
BUTLER COUNTY

Street Address: 122 S. Front Street
Lazarus Gov. Center **TELE:** (614) 644-3020 **FAX:** (614) 644-2329
Mailing Address: Lazarus Gov. Center P.O. Box 1049

Application No: 14-05042

DATE: 1/23/2001

ABC Concrete, Inc
Mike Jump
2450 Crescentville Rd
West Chester, OH 45069-3822

Enclosed please find an Ohio EPA Permit to Install which will allow you to install the described source(s) in a manner indicated in the permit. Because this permit contains several conditions and restrictions, I urge you to read it carefully.

The Ohio EPA is urging companies to investigate pollution prevention and energy conservation. Not only will this reduce pollution and energy consumption, but it can also save you money. If you would like to learn ways you can save money while protecting the environment, please contact our Office of Pollution Prevention at (614) 644-3469.

You are hereby notified that this action by the Director is final and may be appealed to the Ohio Environmental Review Appeals Commission pursuant to Chapter 3745.04 of the Ohio Revised Code. The appeal must be in writing and set forth the action complained of and the grounds upon which the appeal is based. It must be filed within thirty (30) days after the notice of the Directors action. A copy of the appeal must be served on the Director of the Ohio Environmental Protection Agency within three (3) days of filing with the Commission. An appeal may be filed with the Environmental Review Appeals Commission at the following address:

Environmental Review Appeals Commission
236 East Town Street, Room 300
Columbus, Ohio 43215

Very truly yours,

Thomas G. Rigo

Thomas G. Rigo, Manager
Field Operations and Permit Section
Division of Air Pollution Control

CC: **USEPA** **HCDES**

FINAL PERMIT TO INSTALL 14-05042

Application Number:	14-05042
APS Premise Number:	1409080928
Permit Fee:	**$2000**
Name of Facility:	ABC Concrete, Inc
Person to Contact:	Mike Jump
Address:	2450 Crescentville Rd West Chester, OH 45069-3822

Location of proposed air contaminant source(s) [emissions unit(s)]:
600 Augsburger Road
Hamilton, **Ohio**

Description of proposed emissions unit(s):
Concrete Batch Plant (P901), Plant Roadways and Parking Areas (F001), Storage Piles (F002) and Material Handling (F003).

The above named entity is hereby granted a Permit to Install for the above described emissions unit(s) pursuant to Chapter 3745-31 of the Ohio Administrative Code. Issuance of this permit does not constitute expressed or implied approval or agreement that, if constructed or modified in accordance with the plans included in the application, the above described emissions unit(s) of environmental pollutants will operate in compliance with applicable State and Federal laws and regulations, and does not constitute expressed or implied assurance that if constructed or modified in accordance with those plans and specifications, the above described emissions unit(s) of pollutants will be granted the necessary permits to operate (air) or NPDES permits as applicable.

This permit is granted subject to the conditions attached hereto.

Ohio Environmental Protection Agency

Director

Part I - GENERAL TERMS AND CONDITIONS

A. Permit to Install General Terms and Conditions

1. Compliance Requirements

The emissions unit(s) identified in this Permit to Install shall remain in full compliance with all applicable State laws and regulations and the terms and conditions of this permit.

2. Reporting Requirements Related to Monitoring and Recordkeeping Requirements

The permittee shall submit required reports in the following manner:

a. Reports of any required monitoring and/or recordkeeping information shall be submitted to the appropriate Ohio EPA District Office or local air agency.

b. Except as otherwise may be provided in the terms and conditions for a specific emissions unit, quarterly written reports of (a) any deviations (excursions) from emission limitations, operational restrictions, and control device operating parameter limitations that have been detected by the testing, monitoring, and recordkeeping requirements specified in this permit, (b) the probable cause of such deviations, and (c) any corrective actions or preventive measures which have been or will be taken, shall be submitted to the appropriate Ohio EPA District Office or local air agency. If no deviations occurred during a calendar quarter, the permittee shall submit a quarterly report, which states that no deviations occurred during that quarter. The reports shall be submitted quarterly, i.e., by January 31, April 30, July 31, and October 31 of each year and shall cover the previous calendar quarters. (These quarterly reports shall exclude deviations resulting from malfunctions reported in accordance with OAC rule 3745-15-06.)

3. Records Retention Requirements

Each record of any monitoring data, testing data, and support information required pursuant to this permit shall be retained for a period of five years from the date the record was created. Support information shall include, but not be limited to, all calibration and maintenance records and all original strip-chart recordings for continuous monitoring instrumentation, and copies of all reports required by this permit. Such records may be maintained in computerized form.

4. Inspections and Information Requests

The Director of the Ohio EPA, or an authorized representative of the Director, may, subject to the safety requirements of the permittee and without undue delay, enter upon the premises of this source at any reasonable time for purposes of making inspections, conducting tests, examining records or reports pertaining to any emission of air contaminants, and determining compliance with any applicable State air pollution laws and regulations and the terms and conditions of this permit. The permittee shall furnish to the Director of the Ohio EPA, or an authorized

representative of the Director, upon receipt of a written request and within a reasonable time, any information that may be requested to determine whether cause exists for modifying, reopening or revoking this permit or to determine compliance with this permit. Upon verbal or written request, the permittee shall also furnish to the Director of the Ohio EPA, or an authorized representative of the Director, copies of records required to be kept by this permit.

5. Scheduled Maintenance/Malfunction Reporting

Any scheduled maintenance of air pollution control equipment shall be performed in accordance with paragraph (A) of OAC rule 3745-15-06. The malfunction of any emissions units or any associated air pollution control system(s) shall be reported to the appropriate Ohio EPA District Office or local air agency in accordance with paragraph (B) of OAC rule 3745-15-06. Except as provided in that rule, any scheduled maintenance or malfunction necessitating the shutdown or bypassing of any air pollution control system(s) shall be accompanied by the shutdown of the emissions unit(s) that is (are) served by such control system(s).

6. Permit Transfers

Any transferee of this permit shall assume the responsibilities of the prior permit holder. The appropriate Ohio EPA District Office or local air agency must be notified in writing of any transfer of this permit.

7. Air Pollution Nuisance

The air contaminants emitted by the emissions units covered by this permit shall not cause a public nuisance, in violation of OAC rule 3745-15-07.

8. Termination of Permit to Install

This Permit to Install shall terminate within eighteen months of the effective date of the Permit to Install if the owner or operator has not undertaken a continuing program of installation or modification or has not entered into a binding contractual obligation to undertake and complete within a reasonable time a continuing program of installation or modification. This deadline may be extended by up to 12 months if application is made to the Director within a reasonable time before the termination date and the party shows good cause for any such extension.

9. Construction of New Sources(s)

The proposed emissions unit(s) shall be constructed in strict accordance with the plans and application submitted for this permit to the Director of the Ohio Environmental Protection Agency. There may be no deviation from the approved plans without the express, written approval of the Agency. Any deviations from the approved plans or the above conditions may lead to such sanctions and penalties as provided under Ohio law. Approval of these plans does not constitute an assurance that the proposed facilities will operate in compliance with all Ohio laws and regulations. Additional facilities shall be installed upon orders of the Ohio

Environmental Protection Agency if the proposed sources are inadequate or cannot meet applicable standards.

If the construction of the proposed emissions unit(s) has already begun or has been completed prior to the date the Director of the Environmental Protection Agency approves the permit application and plans, the approval does not constitute expressed or implied assurance that the proposed facility has been constructed in accordance with the approved plans. The action of beginning and/or completing construction prior to obtaining the Director's approval constitutes a violation of OAC rule 3745-31-02. Furthermore, issuance of the Permit to Install does not constitute an assurance that the proposed source will operate in compliance with all Ohio laws and regulations. Approval of the plans in any case is not to be construed as an approval of the facility as constructed and/or completed. Moreover, issuance of the Permit to Install is not to be construed as a waiver of any rights that the Ohio Environmental Protection Agency (or other persons) may have against the applicant for starting construction prior to the effective date of the permit. Additional facilities shall be installed upon orders of the Ohio Environmental Protection Agency if the proposed facilities prove to be inadequate or cannot meet applicable standards.

10. Public Disclosure

The facility is hereby notified that this permit, and all agency records concerning the operation of this permitted source, are subject to public disclosure in accordance with OAC rule 3745-49-03.

11. Applicability

This Permit to Install is applicable only to the emissions unit(s) identified in the Permit to Install. Separate application must be made to the Director for the installation or modification of any other emissions unit(s).

12. Best Available Technology

As specified in OAC Rule 3745-31-05, all new sources must employ Best Available Technology (BAT). Compliance with the terms and conditions of this permit will fulfill this requirement.

13. Source Operation and Operating Permit Requirements After Completion of Construction

This facility is permitted to operate each source described by this Permit to Install for a period of up to one year from the date the source commenced operation. This permission to operate is granted only if the facility complies with all requirements contained in this permit and all applicable air pollution laws, regulations, and policies. Pursuant to OAC Chapter 3745-35, the permittee shall submit a complete operating permit application within thirty (30) days after commencing operation of the emissions unit(s) covered by this permit.

14. Construction Compliance Certification

The applicant shall provide Ohio EPA with a written certification (see enclosed form) that the facility has been constructed in accordance with the Permit to Install application and the terms and conditions of the Permit to Install. The certification shall be provided to Ohio EPA upon completion of construction but prior to startup of the source.

15. Fees

The permittee shall pay fees to the Director of the Ohio EPA in accordance with ORC section 3745.11 and OAC Chapter 3745-78. The permittee shall pay all applicable Permit to Install fees within 30 days after the issuance of this Permit to Install.

B. Permit to Install Summary of Allowable Emissions

The following information summarizes the total allowable emissions, by pollutant, based on the individual allowable emissions of each air contaminant source identified in this permit.

SUMMARY (for informational purposes only)
TOTAL PERMIT TO INSTALL ALLOWABLE EMISSIONS

Pollutant	Tons Per Year
PM	15.0
PM-10	15.0

Emissions Unit ID: **P901**

PART II - SPECIAL TERMS AND CONDITIONS FOR SPECIFIC EMISSIONS UNIT(S)

A. Applicable Emissions Limitations and/or Control Requirements

1. The specific operations(s), property, and/or equipment which constitute this emissions unit are listed in the following table along with the applicable rules and/or requirements and with the applicable emissions limitations and/or control measures. Emissions from this unit shall not exceed the listed limitations, and the listed control measures shall be specified in narrative form following the table.

Operations, Property, and/or Equipment
P901 - 300 tons/hr Concrete Batch Plant with Baghouse - unloading to cement/flyash silos w/fabric filter
Sand/aggregate transfer to elevated bins
Transit mix truck loading w/fabric filter
Cement, flyash and sand and aggregate weigh hopper loading w/fabric filter

Emissions Unit ID: **P901**

Applicable Rules/Requirements		Applicable Emissions Limitations/Control Measures
OAC rule 3745-31-05(A)(3)		4.05 lbs/hr PM 5.06 TPY PM 4.05 lb/hr PM10 5.06 TPY PM10
	OAC rule 3745-31-05(A)(3)	The requirements of this rule also include compliance with the requirements of OAC rule 3745-17-07(A)(1).
OAC rule 3745-17-07(A)(1)		See term A.2.2.b.
OAC rule 3745-17-11(B)		The emission limitation specified by this rule is less stringent than the emission limitation established pursuant to OAC rule 3745-31-05(A)(3).
	OAC rule 3745-17-07(A)(1)	
OAC rule 3745-31-05(A)(3)	OAC rule 3745-17-11(B)	2.67 lbs/hr PM 3.34 TPY PM 2.67 lbs/hr PM10 3.34 TPY PM10 0.030 grain of PM/dscf from the fabric filter outlet See terms A.2.2.c., A.2.2.d. and A.2.2.f.
	OAC rule 3745-31-05(A)(3)	The requirements of this rule also include compliance with the requirements of OAC rule 3745-17-07(A)(1)
OAC rule 3745-17-07(A)(1)		See term A.2.2.b
OAC rule 3745-17-11(B)		The emission limitation specified by this rule is less stringent than the

emission limitation established pursuant to OAC rule 3745-31-05(A)(3).	
0.87 lb/hr PM 1.09 TPY PM 0.87 lb/hr PM10 1.09 TPY PM10 0.030 grain of PM/dscf from the fabric filter outlet See terms A.2.2.c. and A.2.2.e.	
The requirements of this rule also include compliance with the requirements of OAC rule 3745-17-07(A)(1) See term A.2.2.b	
The emission limitation specified by this rule is less stringent than the emission limitation established pursuant to OAC rule 3745-31-05(A)(3).	
4.35 lbs/hr PM 5.44 TPY PM 4.35 lbs/hr PM105.44 TPY PM10 See terms A.2.2.a and A.2.2.c.	

2. Additional Terms and Conditions

2.a Sand and aggregate shall be maintained in a moist condition in order to minimize or eliminate visible emissions of fugitive dust.

2.b Visible particulate emissions from any stack shall not exceed 20 percent opacity, as a six-minute average, except as specified by rule.

2.c Visible particulate emissions of fugitive dust from any fugitive dust emissions point shall not exceed twenty percent (20%) opacity as a three-minute average.

2.d The cement/flyash weigh hopper shall be partially enclosed and vented to a fabric filter with a 95% control efficiency.

2.e The transit mix truck loading station shall be partially enclosed and vented to a fabric filter with a 95% control efficiency.

2.f The sand/aggregate weigh hopper shall be partially enclosed in order to minimize or eliminate visible emissions of fugitive dust.

2.g The hourly emission limitations outlined above are based upon the emissions unit's potential to emit. Therefore, no hourly records are required to demonstrate compliance with these limits.

2.h Compliance with OAC rule 3745-31-05(A)(3) shall be demonstrated by partial enclosure of the transit mix truck loading station and sand and aggregate weigh hopper, the use of a fabric filter, visible emission limitations and production limits.

B. Operational Restrictions

1. The maximum concrete production rate for this emissions unit shall not exceed 750,000 tons per year.

C. Monitoring and/or Recordkeeping Requirements

1. The permittee shall maintain monthly records of the amount of concrete produced in this emissions unit.

D. Reporting Requirements

1. The permittee shall submit annual reports that identify any exceedances of the annual production rate limitation, as well as the corrective actions that were taken to achieve compliance. If no exceedances occur a report stating so is required. These reports shall be submitted by January 31 of each year.

E. Testing Requirements

1. Compliance with the emission and production limitations in Section A.1. and A.2. of these terms and conditions shall be determined in accordance with the following methods:

   a. Compliance with the OAC rule 3745-17-07(A)(1) shall be determined by the method specified in 40 CFR Part 60, Appendix A, Method 9.

   b Compliance with the visible particulate emission limitation for fugitive dust shall be determined by the method specified in 40 CFR Part 60, Appendix A, Method 9.

   c. Compliance with the particulate emissions limitations in term A.1. above shall be determined by using the applicable emission factors from AP-42 11.12 (1/95).

   d. Compliance with the production limitation in term B.1. shall be determined by the records maintained pursuant to term C.1.

F. Miscellaneous Requirements

1. None

NEW SOURCE REVIEW FORM B

PTI Number: 14-05042 Facility ID: 1409080928

FACILITY NAME ABC Concrete, Inc

FACILITY DESCRIPTION Concrete Batch Plant (P901), Plant Roadways and Parking Areas (F001), Storage Piles (F002) and Material Handling (F003). CITY/TWP Hamilton

SIC CODE 3273 SCC CODE 3-05-011-01 EMISSIONS UNIT ID P901

EMISSIONS UNIT DESCRIPTION 300 TPH Concrete Batch Plant

DATE INSTALLED 9/2000

EMISSIONS: (Click on bubble help for Air Quality Descriptions)

Pollutants	Air Quality Description	Actual Emissions Rate		PTI Allowable	
		Short Term Rate	Tons Per Year	Short Term Rate	Tons Per Year
Particulate Matter	Attainment	12.0 lbs/hr	15.0	12.0 lbs/hr	15.0
PM_{10}	Attainment	12.0 lbs/hr	15.0	12.0 lbs/hr	15.0
Sulfur Dioxide					
Organic Compounds					
Nitrogen Oxides					
Carbon Monoxide					
Lead					
Other: Air Toxics					

APPLICABLE FEDERAL RULES:

NSPS? NESHAP? PSD? OFFSET POLICY?

WHAT IS THE BAT DETERMINATION, AND WHAT IS THE BASIS FOR THE DETERMINATION?
Partial enclosure of the transit mix truck loading station and sand and aggregate weigh hopper, the use of a fabric filter, visible emission limitations and production limits.

IS THIS SOURCE SUBJECT TO THE AIR TOXICS POLICY? No

OPTIONAL: WHAT IS THE CAPITAL COST OF CONTROL EQUIPMENT? $

TOXIC AIR CONTAMINANTS

Ohio EPA's air toxics policy applies to contaminants for which the American Conference of Governmental Industrial Hygienists (ACGIH) has a listed threshold limit value.

AIR TOXICS MODELING PERFORMED*? _____ YES X NO

IDENTIFY THE AIR CONTAMINANTS: _____

NEW SOURCE REVIEW FORM B

PTI Number: 14-05042 Facility ID: 1409080928

FACILITY NAME ABC Concrete, Inc

FACILITY DESCRIPTION	Concrete Batch Plant (P901), Plant Roadways and Parking Areas (F001), Storage Piles (F002) and Material Handling (F003).	CITY/TWP	Hamilton

Ohio EPA Permit to Install Information Form Please describe below any documentation which is being submitted with this recommendation (must be sent the same day). Electronic items should be submitted with the e-mail transmitting the PTI terms, and in software that CO can utilize. If mailing any hard copy, this section must be printed as a cover page. All items must be clearly labeled indicating the PTI name and number. Submit hard copy items to **Pam McGraner**, AQM&P, DAPC, Central Office, and electronic files to **airpti@epa.state.oh.us**

Please fill out the following. If the checkbox does not work, replace it with an 'X'	Electronic	**Additional information** File Name Convention (your PTI # plus this letter)	Hard Copy	None
Calculations (required)	☐	0000000**c**.wpd	☒	☐
Modeling form/results	☐	0000000**s**.wpd	☐	☒
PTI Application (complete or partial)*	☐	0000000**a**.wpd	☐	☒
BAT Study	☐	0000000**b.**wpd	☐	☒
Other/misc.	☐	0000000**t**.wpd	☐	☒

* Mandatory for netting, PSD, nonattainment NSR, 112(g), 21-07(G)(9)(g) and 21-09(U)(2)(f) - 2 complete copies.

Please complete (see comment bubble to the left for additional instructions):

NSR Discussion

PTI 14-05042

ABC Concrete, Inc. Plant #2
2450 Crescentville Road
West Chester, OH 45069

Facility ID: 1409080928

ABC Concrete Inc. produces concrete. This PTI is for a new concrete batch plant. The aggregate storage piles and plant roadways & parking areas associated with the plant were shown to have emissions below 10 lb/day Therefore, they qualify as de-minimus sources and do not need to be permitted. The emissions from the new plant will be fugitive and stack particulate matter. The OAC rules governing the emissions units are 3745-31-05 (BAT), 3745-17-07 and 3745-17-11.

For calculation of actual and potential emissions, see the attached sheets. Hourly emissions are based on a maximum hourly production rate of 300 tons of concrete per hour. Emission factors are from appropriate sections of AP-42 for roadways and parking areas, storage piles and a concrete batch plant.

BAT is satisfied by the unloading to cement/flyash silos, cement/flyash weigh hopper loading and transit mix truck loading being vented to a fabric filter. In addition, the transit mix truck loading station and sand and aggregate weigh hopper shall be partially enclosed. Finally, BAT shall also be demonstrated by the visible emission limitations and the use of dust suppressants.

NEW SOURCE REVIEW FORM B

PTI Number: 14-05042 Facility ID: 1409080928

FACILITY NAME ABC Concrete, Inc

FACILITY DESCRIPTION	Concrete Batch Plant (P901), Plant Roadways and Parking Areas (F001), Storage Piles (F002) and Material Handling (F003).	CITY/TWP	Hamilton

The particulate emissions for this facility will be limited to 15.0 TPY. In addition, PM10 will be limited to 15.0 TPY

The permit fee is	$1000.00	P901 Concrete batch plant (based on PWR of 300 tons per hour).
	X 2	Installing and Operating the source before the PTI was approved.
Total:	$2000.00	

Prepared by: Chad Powell

Date prepared: January 4, 2001

Please complete for these type permits (For PSD/NSR Permit, place mouse over this text):

☐ **Synthetic Minor Determination and/or** ☐ **Netting Determination**

Permit To Install **ENTER PTI NUMBER HERE**

A. Source Description

B. Facility Emissions and Attainment Status

C. Source Emissions

D. Conclusion

PLEASE PROVIDE ADDITIONAL NOTES OR COMMENTS AS NECESSARY:

NONE

Please complete:

SUMMARY (for informational purposes only)

TOTAL PERMIT TO INSTALL ALLOWABLE EMISSIONS

Pollutant	Tons Per Year
PM	15.0
PM-10	15.0